Alternative 3

A. Reconfigure Grand Avenue Interchange to partial cloverleaf ramps on SR-60

B. Widen Grand Avenue and reconstruct the Grand Avenue OC Bridge over SR-60

C. Construct a westbound auxiliary lane on SR-60 from SR-57

D. Construct a new slip on-ramp to westbound SR-60 from Grand Avenue

E. Construct a new eastbound bypass off-ramp to Grand Avenue

F. Construct a new eastbound loop on-ramp on Grand Avenue and extend an eastbound auxiliary lane to the bypass connector.

G. Construct a new eastbound bypass connector on SR-60